



Hampshire County Health Department

HC 71, Box 9

Augusta, WV 26704

(304) 496-9640

Fax: (304) 496-9650

October 28, 2005

Hampshire County Planning Commission
PO Box 883
Romney, WV 26757

Dear Sirs;

This office has reviewed a plat of survey for Robert Williams to create lots 1, 2, 3, 4, and 5 for a subdivision called Mill Creek Knobs, located off Stringtown Road (near Purgitsville) and further described as Tax district Mill Creek, Deed Book 444, Page 237, Tax Map 4, Parcel 35. These lots total 96 acres.

All lots require a percolation test and a sewage disposal area of 10,000 square feet where no development or structures other than the septic system shall be permitted. These lots are to be developed with an individual well and septic to serve a single-family dwelling.

Percolation test results are within limits as set forth by West Virginia CSR 16-1. Six feet soil observation holes indicate no restrictions due to water table or shallow bedrock within the designated sewage disposal area except as noted on the Health Department subdivision application.

The plat of survey dated October 28, 2005 is hereby approved by the Hampshire County Health Department. Any changes or revisions to the Health Department stamped and signed plat, or subsequent final plats approved based upon the approved plat, will make this approval null and void.

This approval is not a permit for individual water systems or individual sewer systems. Applications for permits must be made separately to the Hampshire County Health Department.

Sincerely,


Denson Taketa

cc: Robert Williams

**REPORT SHEET
FOR
PERCOLATION AND SIX FOOT HOLE TESTING**

Subdivision Name Mill Creek Knobs County Hampshire

Total Number of Lots 5 Name of Applicant Robert Williams/RCS, LLC

Name of Certified Installer Responsible for Testing James E. Riggleson

Installer Certification No. 54-04-0016 Installer Signature [Signature]

Address 3410 South Fork Rd. Moorfield WV

26536

Type System	Lot Number	Percolation Test Results (Minutes per Inch of Fall)					Average Results	Six Foot Hole Results		Date Conducted
								Depth to Water	Depth to Rock	
CLI	1	15	20	17	18	18			9/29/05	
CL2	2	42	25	40	20	32			9/29/05	
CLI	3	28	29	35	40	33			9/29/05	
CLI	4	42	38	34	36	38			9/29/05	
CLI	5	42	28	34	38	36			9/29/05	
Letter of Approval for Tract B (not part of subdivision)										
CLI	1	45	42	35	40	41			9/29/05	

(Attach additional pages if needed)