

577-185
Code

DATE JUNE 6, 1977

LOCATION Franklin
Township

1/4; Sec. 4; T. 4S; R. 5E

HARRISON COUNTY HEALTH DEPT.
Rural Route 6, Box 80
Corydon, Indiana
47112

APPLICATION FOR PERMIT FOR INDIVIDUAL SEWAGE SYSTEM

OWNER'S NAME AND MAILING ADDRESS

Chester R. Stem
Lanesville, IN

INSTALLER'S NAME AND ADDRESS

Shewmaker Bros.
Dixie, IN

TELEPHONE _____

TELEPHONE _____

NO. OF BEDROOMS 3 NO. OF BATHS 1 AUTOMATIC WASHER YES ☒ NO ☐

YES	NO		YES	NO	
		WATER:	☒		DISTRIBUTION BOX <u>for man</u>
		CITY	☒		LATERAL FIELD
		WELL	☒		2" GRAVEL ABOVE TILE
		CISTERN	☒		6" GRAVEL BELOW TILE
		SPRING			BASEMENT
		Other:			NEW HOME
					ADDITION TO HOME
			☒		OTHER: <u>(REPAIR)</u>

PERC TEST RESULTS: AVG. N/A INCH IN N/A MINS. SOIL: _____

SEPTIC TANK CAPACITY Existing DRAINFIELD: TRENCH DEPTH 30" TRENCH WIDTH 24"

TOTAL LENGTH OF TILELINE 300 feet USING RIVER GRAVEL (No Crushed Stone)

APPLICATION FOR PERMIT APPROVED ☒ NOT APPROVED _____

DATE: June 6, 1977

SANITARIAN Paul J. Schroeder

FINAL INSPECTION: Approved

DATE: June 17, 1977 R. Schroeder

Sanitarian

NOTE:

On the back draw a plot diagram showing the size and shape of the lot, location of utility buildings, wells, roads, and/or streams within 100 feet of the disposal system, the location of the septic tank, and the location of the drainage field. Approximate distances must be shown from the disposal system to any proposed or existing water lines, wells, streams, and the lot lines.

THE SEWAGE DISPOSAL PERMIT MUST BE APPROVED BEFORE CONSTRUCTION IS STARTED

The maximum length of any one trench is 100 feet.
Six (6) inches of gravel under lateral lines and two (2) inches above pipe.
Must be installed 50 feet or more from water supply lines.
Ten (10) feet or more from property lines.
Distances between trenches — Six (6) feet.
INSPECTION MUST BE MADE BEFORE THE LATERAL LINES ARE COVERED. ☒

Call for inspection either the day before or between 8:00 and 9:00 in mornings, 738-3237.

If construction is not started within a period of one year, this permit is void.

77185

W/24"
TRENCHES

