| M~ | TARRANT REGIONAL WATER DISTRICT 140 FM 416, Streetman, Texas 75859 903-389-3928 Fax # 903-389-7587 TRWD USE ONLY APPLICATION NO. |
|-----|--|
| | APPLICATION FOR ON-SITE SEWAGE FACILITY RECEIPT NO. 7 |
| | TRWD RESERVOIR AMOUNT COUNTY OF INSTALLATION TO AMOUNT AMOUNT |
| 1. | PROPERTY OWNER'S NAME: LOVE Janet L. (LAST) (FIRST) (MIDDLE) |
| 2. | PERMANENT MAILING ADDRESS: 3009 Huntington Ct. Wayahack |
| 3. | TELEPHONE NO. DURING DAY: (214) 364-8611 |
| 4. | SITE ADDRESS: 269 Jackson Circle, Kerns TY. 75 (STREET) (CITYISTATE) (ZIP) |
| 5. | PROPERTY DESCRIPTION: LOTNO. 4/ BLOCK SEC SIZE SQ.FT. SUBDIVISION: SWRETWATER RANCHACTEAGE 1.4 Survey Hearn - 42 |
| 6. | SOURCE OF WATER: Private Well Public Water Supply Onatfield (NAME OF SUPPLIER) |
| 7. | SINGLE FAMILY RESIDENCE: No. of Bedrooms 3 Living Area (sq. ft.) 895.5 DESIGNED MAXIMUM DAILY WATER CONSUMPTION (gpd): 300 |
| 8. | COMMERCIAL/INSTITUTIONAL (including multi-family residences) TYPE: |
| | NO. OF EMPLOYEES/OCCUPANTS/UNITS: 7 2 DAYS OCCUPIED PER WEEK: 12 |
| | DESIGNED MAXIMUM DAILY WATER CONSUMPTION (gpd): 4 2 |
| 9. | IS AN ORGANIZED SEWAGE COLLECTION WITHIN 300 FEET?YesNo |
| 10. | DESIGNER: Will Hill LICENSE NO.: 1361 |
| • | PHONE NO.: 903 874 6 3945 |
| 11. | INSTALLER: Perry Richtola REGISTRATION NO.: 653// |
| | PHONE NO.: 903 874 6006 |

sewerage facility and that a permit to operate the facility will be granted following successful inspection of the installed system which indicates that the system was installed in compliance with TCEQ'S On-Site Sewage Facility Rules (OSSF) and the Diștrict's Waste Contyğl Order.

(SIGNATURE OF AUTHORIZED DISTRICT REPRESENTATIVE)

_//- 26-63 (DATE)

TARRANT REGIONAL WATER DISTRICT

140 FM 416, Streetman, Texas 75859 903-389-3928

AUTHORIZATION TO CONSTRUCT AN ON-SITE SEWAGE FACILITY

Application Number

RC 1203103

Property Owner

Janet L. Love

Mailing Address

3009 Huntington Ct.

Waxahachie, Texas 75144

Property Location

Lot 41 Sweetwater Ranch II

OS-8058

269 Jackson Circle Kerens, Texas 75144

Navarro County, Texas

This serves to notify all persons that an on-site sewerage facility application, related technical data, and the appropriate fee have been received by the Tarrant Regional Water District (District) from the property owner. The application has been reviewed for technical and administrative consideration against the standards set forth by the District. Approval is hereby granted for the construction as shown on the submitted plans.

Any modifications to submitted plans require approval by the Tarrant Regional Water District prior to installation.

You or your installer must contact the District office at 903-389-3928 between 7:30 A.M. to 8:30 A.M. to arrange for the required facility inspection. Calls after 8:30 A.M. may result in inspection being delayed until the next working day. The authorization to construct is valid for one year from the date of issue of an application. If a final inspection has not been performed within one year of issue, a new application and fee will be required.

Comments: The following design is based upon the minimum standards set forth by the Texas Commission on Environmental Quality and is based on a maximum daily flow of 300 gallons, the use of water saving devices is required.

Authorized District Representative

_____12-22-03

Date

TARRANT REGIONAL WATER DISTRICT

140 FM 416, Streetman, Texas 75859 903-389-3928

NOTICE OF APPROVAL OF ON-SITE SEWAGE FACILITY

PERMIT # RC 1203103

| | | .203103 | |
|---|---|--|---|
| | • | | |
| Property Owner | Janet Love | · · · | |
| Mailing Address | 3009 Huntington | Ct. | · |
| | Waxahachie, Tex | cas 75144 | |
| Property Location | Lot 41 Sweetwat | er Ranch II | |
| | | | <u>:-</u> |
| | Navarro | County, Tx. | |
| | | • | |
| Quality (TCEQ) and to Site Sewage Facility facility. ANY MODIFICAT | the District Waste Contro Permit is issued for the IONS TO THE SYST | ents of the Texas Commission of the Texas Commission of the above identification of th | al Water District Ontified on-site sewage S COMPONENTS, |
| ADDITIONAL INFO | RMATION: | | |
| | | • | · |
| | | | · |
| | | | |
| Chis Bola | OS-8058 | | |
| Authorized District Repre | | | |
| 12-23-6 | | | |

TARRANT REGIONAL WATER DISTRICT

140 FM 416, Streetman, Texas 75859 903-389-3928

ON-SITE SEWAGE FACILITY PROGRAM LOW PRESSURE PIPE SYSTEM INSPECTION REPORT

| PROPERTY OWNER: Janet Love PERMIT NUMBER: RC 1203 | 103 | |
|--|---------------|-----|
| | | |
| I. SEWER | Y | N |
| CLEANOUTS PROPERLY INSTALLED: | 1/ | |
| PROPER TYPE PIPE FROM STRUCTURE TO DISPOSAL SYSTEM: | 1 | · |
| SLOPE OF SEWER 1/8 INCH PER FOOT MINIMUM: | | |
| II. SEPTIC TANK | Y | N |
| TANK SIZE REQUIRED: 1,250 gal. TANK SIZE INSTALLED: 1)75% 1)500 | ** | ** |
| TYPE: Concrete MANUFACTURER: Ellison | ** | ** |
| RISERS PROVIDED ON TANKS BURIED GREATER THAN 12": | 11 | |
| INLET FLOWLINE GREATER THAN 3" ABOVE OUTLET FLOWLINE: | | |
| OUTLET LIQUID PENETRATION 1/4 TO 1/2 TOTAL LIQUID DEPTH: | 1 | |
| "T" PROVIDED ON INLET AND OUTLET: | 1 | |
| IF SINGLE TANK, ARE 2 COMPARTMENTS PROVIDED? | $\frac{1}{2}$ | 1/1 |
| III. PUMP TANK | Y | N |
| TANK SIZE REQUIRED: 500 gal TANK SIZE INSTALLED: 500 504 4 | ** | ** |
| TYPE: Concrete MANUFACTURER: 6///60 | ** | ** |
| TYPE AND SIZE OF PUMP: Grun 65 AP-12 + HP | **. | ** |
| IV. DRAINFIELD | Y | N |
| LATERAL LINE SIZE: D'"PVC 1 1/4"PVC 1 1/2"PVC OTHER SPECIFY | ** | ** |
| SUPPLY LINE DIAMETER: 217 | ** | ** |
| MANIFOLD DIAMETER: 210 | ** | ** |
| AREA REQUIRED: 2340 sqft AREA INSTALLED: 2340 fg | ** | ** |
| EXCAVATION DEPTH: 24'n WIDTH: Sin LENGTH: 780 ft | ** | ** |
| DISTANCE BETWEEN EXCAVATIONS: 3.5 FT | ** | ** |
| PROPER PLACEMENT OF DAMS | | - |
| TYPE OF MEDIA: BROCK | ** | ** |
| DEPTH OF MEDIA: 17:0 | ** | ** |
| PROPER BARRIER BETWEEN MEDIA AND BACKFILL: | | - |
| RISERS INSTALLED FOR HEAD PRESSURE ADJUSTMENT: | 1/ | |
| DATE HEAD PRESSURE WAS SET: | ** | ** |
| ZONES INSTALLED PROPERLY. Yes HOW MANY? | ** | ** |
| PROPER CONTROL VALVES INSTALLED. Ye 5 HOW MANY? / | ** | ** |
| MINIMUM REQUIRED SETBACK DISTANCES MET? IF NOT, LIST DEFICIENCIES. | L | |
| AUDIO/VISUAL ALARMS INSTALLED: | 1 / | |
| COMMENTS: | 1 5 | |
| | | _ |
| C. Polls. | | |
| INSPECTED BY: | | |



BUILDING PERMIT


Nº 0735


| | COUNTY OF NAVA | RRO, TEXAS | | ADDRESS |
|--|---------------------|--------------------------------|---|-----------------------|
| JOB ADDRESS 2 U | 9 Orickson | . Cr. Ke | rens 45144 | DORESS |
| LOT NO. | SUBDIVISION | tueater Ru | mehPh. II gra | 2- |
| OWNER DMITH Caroll | Love 1916 Wr | odale Cr. C | Mu Hell 75104 | 3775 |
| CONTROJOR JAMA MC | Dowell 2 | Vaefahari | PHONE | 4 |
| ELECTRICAL SULL | ADDRESS | | PHONE | |
| PLUMBING Sell | ADDRESS | | PHONE | _ |
| MECHANICAL SILL | ADDRESS | | FRONE | |
| USE OF BUILDING | ral | | | _ |
| CLASS OF WORK: NEW | ADDITION ALT | ERATION RE | PAIR DEMOLISH | _ |
| DESCRIBE WORK: | newhame | <u> </u> | | _ |
| | | | | |
| | | | | |
| 0.4 | SQ. FT. | | NO. OF STORIES | |
| Will Stone | NO. OF BATHS | 5 | FOUNDATION | |
| NO. OF ROOMS 3.BR | SPRINKLERS REQUIRE | /2 | PARKING SPACES | |
| ROOF LOMP. | ZONING | | OCCUPANCY GROUP | |
| NO, OF DWELLING UNITS | SF | I DEDEBY CERTIF | FY THAT I HAVE READ AND EXAM | MINED THIS |
| NOTICE | | APPLICATION AND ALL PROVISIONS | KNOW THE SAME TO BE TRUE AND OF LAWS AND ORDINANCES GOVE | CORRECT. |
| THIS PERMIT BECOMES NULL A CONSTRUCTION AUTHORIZED | IS NOT COMMENCED | HEREIN OR NOT | VILL BE COMPLIED WITH WHETHER T. THE GRANTING OF A PERMIT VE AUTHORITY TO VIOLATE OR C NY OTHER STATE OR LOCAL LAW F | DOES NOT ANCEL THE |
| WITHIN 6 MONTHS, OR IF CONS | D FOR A PERIOD OF 1 | CONSTRUCTION C | OR THE PERFORMANCE OF CONSTRI | JCTION. |
| YEAR AT ANY TIME AFTER WOR | MIT SHOULD NOT BE | Lant | . Some | |
| CONSTRUED BY ANY PERSON RUILDING OR CONSTRUCT | AS AN APPROVAL OF | APPROVED FOR 1550 | A7,525 W PERMIT FEE S | 30.40 |
| METHODS, OR MATERIALS. | | Michiel | ennon 2-11. | -03 |
| SPECIAL CONDITIONS: | | | | |
| | | | | |
| THIS BECOMES YOUR PERMIT WE | HEN APPROVED FOR IS | SUANCE | | |
| | | | | |
| | | | | |


ON-SITE SEWAGE FACILITY SOIL SURVEY REPORT INFORMATION

| Property | Owner's Name <u>Janet I</u> | _ove | | | | · - · · · · · · · · · · · · · · · · · · | · |
|-----------|--|---|-----------------------------------|-----------------------|--------------------|--|---|
| Mailing . | Address269 Ja | ckson Cirle | | | | | |
| City, Sta | te, Zip <u>Kerens</u> | , TX | | | | | |
| Site Loc | ation 269 Jac | kson Circle; Swe | etwater Ranch_ | | | | |
| County_ | Navarr | o <u>.</u> | | | | | |
| (FOR HOLI | E#1) | | | <u>,</u> | | | |
| DEPTH | TEXTURE | CLASS | STRUCTURE | WATER TABLE | SLOPE 0-30% | * SOIL SERIES | * SOIL ABSORPTION |
| in. | i.e. Loamy Sand, Sandy Loam, Loam, Silty Clay Loam, Sandy Clay , or Clay. | per USDA Chart i.e. la,lb,ll,lll,or IV | | | of overall | Soil Survey | LIMITATION RATING i.e. Fair, Moderate, Severe |
| 00 - 16 | Clay | IV | | No | 3.70% | | Severe |
| 16 - 30 | Clay Loam | Ш | | No | | | Moderate |
| 30 - 36 | Sandy Loam | П | | No | | | Fair |
| | | | | | | | |
| (FOR HOLI | LATION IS: CLASS _ E #2) | [Note C | lass la & IV are u | T | 1 | | <u>.</u> |
| DEPTH | TEXTURE | CLASS | STRUCTURE | WATER TABLE | SLOPE 0-30% | * SOIL SERIES | * SOIL ABSORPTION |
| in. | i.e. Loamy Sand, Sandy Loam, Loam, Silty Clay Loam, Sandy Clay , or Clay. | per USDA Chart i.e. la,lb,ll,lll,or IV | | PRESENT Yes / No | Maximum of overall | per County Soil Survey | LIMITATION RATING i.e. Fair, Moderate, Severe |
| 00 - 12 | Clay | IV | #0 · | No | 3.70% | and the same | Severe |
| 12 - 36 | Clay Loam | Ш | | No | ع ما ما وي | " TELEVISION | Moderate |
| | | | | | \$ 5 × 1 | The state of the s | \$2 |
| | | | | | WILL! | MW. HILL | |
| | | | | | J. 655. | 361 | Ĉ. |
| THE MO | an be found in the Count OST RESTRICTIVE SO LATION IS: CLASS | IL CLASS FOUR | ND ONE FOOT : Class Ia & IV ar | BELOW e unsuitable | THE DEP | THOF THE | |
| | ATION PERFORMED DE SOIL SURVEY: | | Man Hi | | | stered Sanita | |

Sweetwater Ranch Ph. II







Janet Love * 269 Jackson Circle * Sweetwater Ranch

| Daily Waste Flow | 360 gal./day |
|--------------------------------------|--|
| Septic Tank Size | 1250 gal. |
| Pumping Tank Size | 500 gal. |
| Effluent Loading Rate | 0.2 gal./ sq. ft./day |
| Absorption Area | 2340 sq. ft. |
| Total Length of laterals | 780 ft. |
| Lateral Diameter | 1 in. sch. 40 |
| Lateral Configuration & Hole Spacing | see attached diagram |
| Supply Line Length | 157 ft. |
| Supply Line Diameter | 2 in. sch. 40 |
| Manifold Placement | End |
| Hole Size | 1/8 in. |
| Number of Holes | 113 |
| Flow per Hole | see attached chart |
| Total Flow | 29.9 GPM |
| Elevation Head | 11.7 ft. |
| Friction Head | 2.9 ft. |
| Pressure Head | 1.5 ft. |
| Total Head | 16.1 ft. |
| Pump Requirements | 30.0 gpm. @ 16.1 ft. head |
| Suggested Pumps | Barnes BP314 1/3HP Grundfos AP12 1/2 HP |
| Storage Volume in Laterals | 32.0 gal. |
| Storage Volume in Supply | 25.4 19.6 gal. |
| Total Storage | 57.4 51.6 gal. |
| Dosing Volume | 95.0 gal. |
| Dosing Depth | 7.5 in. 1 OF 7 |

YES

NO

20 yds.

YES

Check Valve Needed?

Anti-Siphon Hole Needed?

Approximate Quantity of Rock

Effluent Filter Recommended Zabel A1800

Janet Love * 269 Jackson Circle * Sweetwater Ranch

| | | | | | , | | | | | |
|------------------|----------------|-----------------|---------------------------|--------------|-----------------|--------------|----------------------|------------------|-------------------|--------------------------|
| | | | | | | | | | | |
| Level or Zone | Line Number | *Depth (In.) | Pressure Head (ft.) | Length (ft.) | Number Holes | Hole Size | FLOW GPM/ hole | RATE GPM/line | GPM/ ftline | Hole Spacing (ft.) |
| A | 1 | 18 | 1.5 | 60 | 11 | 0 1/8 | 0.22 | 2.42 | 0.04 | 5.45 |
| A | 2 | 18 | 1.5 | 60 | 11 | 0 1/8 | 0.22 | 2.42 | 0.04 | 5.45 |
| A | 3 | 18 | 1.5 | 60 | 11 | 0 1/8 | 0.22 | 2.42 | 0.04 | 5.45 |
| A | 4 | 18 | 1.5 | 60 | 11 | 0 1/8 | 0.22 | 2.42 | 0.04 | 5.45 |
| В | 5 | 18 | 2 | 60 | 9 | 0 1/8 | 0.26 | 2.34 | 0.039 | 6.7 |
| В | 6 | 18 | 2 | 60 | 9 | 0 1/8 | 0.26 | 2.34 | 0.039 | 6.7 |
| В | 7 | 18 | 2 | 60 | 9 | 0 1/8 | 0.26 | 2.34 | 0.039 | 6.7 |
| C | 8 | 18 | 2.5 | 60 | 8 | 0 1/8 | 0.29 | 2.32 | 0.039 | 7.5 |
| C | 9 | 18 | 2.5 | 60 | 8 | 0 1/8 | _ 0.29 | 2.32 | 0.039 | 7.5 |
| D | 10 | 18 | 3 | 60 | 7 | 0 1/8 | 0.32 | 2.24 | 0.037 | 8.6 |
| D | 11 | 18 | 3 | 60 | 7 | 0 1/8 | 0.32 | 2.24 | 0.037 | 8.6 |
| E | 12 | 18 | 3.5 | 60 | 6 | 0 1/8 | 0.345 | 2.07 | 0.035 | 10 |
| <u>E</u> | 13 | 18 | 3.5 | 60 | 6 | 0 1/8 | 0.345 | 2.07 | 0.035 | (), 10 |
| | | | | 780 | 113 | | | 29.96 | LIAM W. H 1361 | 2 01 03 W * 1 |
| | | | | | | | | | | |
| | l | | | | | | | . | | |

