

# PFIESTER SEPTIC SYSTEMS & CONSTRUCTION

David L. Pfister  
103 Mercury Street  
Brady, Texas 76825



Phone: 325-597-9693  
Cell: 325-456-3576  
www.pfiesterconstruction.com  
davidpfiester@yahoo.com

August 30, 2016

To: Kenneth Kyle Sr.  
389 US Hwy 84 W  
Goldthwaite, Texas 76844

Subject: Estimate for combined 5BR septic system (pumped drain field)

\$11,200.00

Work description: Conduct soil/site evaluation and send it along with permit application to Mills County TCEQ designated representative (DR) in San Saba, Texas. After receiving authorization to construct from DR, plumb the three buildings on premise to the proposed septic tank location. Dig-out soil and remove rock to required depth utilizing hydraulic hammer. Install 1750 gallon 3 chamber concrete septic tank with 1/2 hp Liberty pump in third chamber. Have electricians wire pump to control box mounted on service pole and then to designated breaker (at owner's expense). Plumb outlet line to leach field and install 340' of 2' x 5' Infiltrator leaching chambers. After inspection from DR, backfill and smooth worksite.

Work start-up date 9/13/16, completion date 9/19/16

Payment terms: \$5600.00 to begin with remaining balance due upon completion.

Please make check payable to Pfister Septic Systems

*Check Paid 4214*

- \*\*\* Not responsible for tree/grass damage or loss
- \*\*\* Not responsible for settling
- \*\*\* Not responsible for damage or replacement of sprinkler systems
- \*\*\* Estimate based on worksite having 5' of suitable soil. Should rock become a factor, the additional costs of hydraulic hammering and rock removal will be assessed on-site with client.

*Kenneth Kyle August 30, 2016*  
client - Kenneth Kyle Sr.

*David L. Pfister*  
David L. Pfister

Texas OSSF License # OS0026533  
Texas Site Evaluator License # OS0027499

**PFIESTER SEPTIC SYSTEMS & CONSTRUCTION**

David L. Pfister  
103 Mercury Street  
Brady, Texas 76825  
Phone: 325-597-9693  
Cell: 325-456-3576  
www.pfiesterconstruction.com  
davidpfiester@yahoo.com



**INVOICE**

August 29, 2016

Bill To:

Kenneth Kyle  
Goldthwaite, Texas

Work Description:

Conduct soil/site evaluation

\$250.00

Texas OSSF Installer II License # OS0026533  
Texas OSSF Site Evaluator License # OS0027499

*PAID IN FULL*  
*[Handwritten Signature]*

Please make check payable to Pfister Septic Systems

**THANK YOU FOR YOUR BUSINESS!**

Balance Due:

**\$250.00**

